Fig. 6. Driving out the first motion shaft with a drift acting through the housing for the third motion shaft front bush bearing. Take care not to damage this housing.

EXAMINATION FOR WEAR

Clutch Cross Shaft Bushes

It is unlikely that these bushes should have worn, but should the cross shaft appear excessively loose in the bushes, new ones must be fitted. These bushes are fitted in two parts with a gap left between the parts, thus providing an oil channel for lubrication via the oiling nipples.

Bearings

ily,

m

The first and third motion shaft ball bearings may become worn after a considerable length of service and should be renewed if there are signs of looseness between inner and outer races.

First and Third Motion Shaft Bush

This bush is fitted with a maximum permissible internal clearance of .003 in. for the third motion shaft. When any appreciable wear above this figure occurs, the bush and shaft should be examined and renewed where necessary.

Third Motion Shaft Sleeve

The phosphor bronze sleeve which carries the first and second (actual) speed gear assemblies must be replaced if the wear between the shaft and sleeve appears excessive. The fitted clearance in a new gearbox is between .00025 and .00175 in.

Laygear Thrust Washers

These washers are designed to permit an end float for the layshaft cluster gears between .001 and .003 in. If the end float exceeds this tolerance, the thrust washers must be renewed. The smaller thrust washer, positioned at the rear, is made in varying thicknesses to allow for correct end float to be obtained.

н10. 94. Е. 2 3

Fig. 7. Synchronising cone.

1. Chamfer to be machined after cone is shrunk into position. 2. Cone.

3. Coupling adapter. 4. Constant mesh gear.

Layshaft and Bushes

The layshaft and layshaft bushes, in the cluster gear assembly, may become worn and need renewal. Both the front and rear bushes have an internal clearance of .002 in.—.003 in. These bushes are a press fit in the laygear.

Gear Synchronising Cones

These cones are "shrunk on" to the first, second and third speed gears (actual), which are normally supplied as a complete unit for spares purposes. Where facilities exist for shrinking on and final machining, cones can be supplied separately. However, care must be taken in fitting if the gear is to operate satisfactorily.

The internal broaching of the cone is calculated to allow for a shrinkage fit on to the gear serrations, and the cone must be heat-expanded before it can be fitted.

When heated to approximately 250 degrees Fahrenheit, expansion will allow the cone to be pressed home on to the gear without damaging the broaching and will




Fig. 8. Cone dimensions.

A. Cone angle 5° 10'. B. Coarse thread turned with .015 in. lead.

C. Cone diameter 2.5 in.

adapter, and this must be facing the cone.

When the cone is in position, t can be done in accordance with the difig. 8. The taper of the cone must be tric with the bore to .001 in.




Fig. 9. Using Service Tool GT.40 to asse balls to a coupling sleeve and sy

ASSEMBLING THE GE

Perfect cleanliness of the gearb before commencing assembly. Alth complete assembly operation has be is advisable for the operator to read the before commencing any work. The the various parts are so interlaced to

To reassemble the gearbox prod

Synchromesh Sub-Assembly

During manufacture both the sp and 3rd (actual) speed coupling slee with their respective synchronisers. of these parts should therefore be fitt

Special guides are available t assembling of the three balls and s chronisers. The guide is of the sa coupling sleeve, see fig. 9.